

OFFICE OF THE EXECUTIVE ENGINEER
Electricity Distribution Division
DEOBAND

ESTIMATE

Name Shri. श्री लखपाल S/o Shri. श्री पिता
Village जीरपुर मापरा P.O. खेडागुवा Block नगाव
Load ने-5 मी (H.P.) Sanction No. 1008202683 Dated 03/09/2022

	Work Involved	Quantity	Rate Per	Amount (Rs.)
14.603	11 KV. lines on P.C.C. Poles	36 मी	Rs. 130/-	39227=
14.603	2 L.T. Line 3 phase on P.C.C. Poles	कोलिस सर्विस	130/-	
3	Extra Cost for section Poles (11 K.V. Line)		-	
4	Extra for last Pole tapping		-	
5	Extra for L.T. tapping		-	
6	Extra cost for 11 K.V. tapping		-	
	Total			39227=
14.542	1 11/0.4 K.V. Substation 10 KVA 2510VA	1	40495/-	31527=
	on PCC Pole structure		94582	
14.621	1 Fixed Charges		7000/-	5000=
2	Variable Charges		5000	
3	System Loading Charges	K.V.A. 270/- Per K.V.A.	300	2400=
	Total			36527/-

JUNIOR ENGINEER

(33 K.V.S. Deoband)

No. _____ Dated _____

Copy forwarded to Divisional Engineer, Electricity Distribution Division-II, Saharanpur for information and necessary action.

ABSTRACT

14.630 Ch. to U.P.P.C.L. Rs.

14.542 Ch. to U.P.P.C.L. Rs. 31527/-

14.621 Ch. to Consumer Rs. 5000/-

14.603 Ch. to Consumer Rs. 36527/-

Checked by DM

Allocation Checked DM

Estimate Sanction No. 136/22-23
Dated _____

अतिरिक्त अधिकारी
विद्युत वितरण खण्ड-देवबन्द

TECHNICAL REPORT

SUMMARY OF MAIN MATERIAL REQUIRED

1. Length of H. T. Line proposed... X Mtr
2. Length of L. T. Line proposed... 36 Mtr
3. Capacity proposed for new S/S... X KVA
4. Capacity of existing S/S... KVA
5. Total Connected load on S/S... 7.5 MHP
6. Sanction load... 7.5 MHP
7. Feeder... Beerpur Feeder
8. 33 KV/11/4 KV Sub-Station... S/S Beerpur

1. Support
2. Conductor
3. Stay Rod 16 MM
4. Stay wire 7/10 SWG
5. L.T. Shack Insulator 75 X 90 MM
6. L.T. Pin Clamp
7. Stay Insulator
8. Stay Clamps
9. Earth Clamps
10. Earth Wire (G.I. wire) 5 MM
11. Earthing Rod 20 MM
12. M.S. Bolts & Nuts
13. P.V.C. Cable 4 X 6 MM
14. 11 KV Pins & Insulator
15. 11 KV Disc & Fittings
16. M.S. Channel 100 X 50
17. M.S. Angle 65 X 65 X 6 MM
18. 11 KV X Arm
19. U Clamps
20. F Clamps
21. Transformer
22. P.V.C. Cable 4 X 6 MM
- 23.
- 24.

NOTE -> प्रस्तावित उपग्रामों की उचित लाइन बनाने में अगर कोई बाधा पाया जाता है तो उपग्रामों की उचित पूर्ण जिम्मेदारी उपग्रामों की होगी न कि विद्युत विभाग की


NOTE -> घरेलू नैसर्गिक स्रोतों पर प्रतीति
LIC No - 312000144568

ROUGH LINE CHART

33/11 KV S/S बीरपुर / बीरपुर नगर

प्रस्तावित
स्रोतों पर प्रतीति ग्राम बीरपुर

36 Mtr
कैबिले लाइन



TIF
25 KVA
प्रतीति लाइन
ग्राम बीरपुर ग्राम
7.5 MHP

उपग्राम अधिकारी
वि. वि. उपग्राम नगर

प्रताप सिंह (अवर अभियन्ता)
33/11 KV S/S बीरपुर
बीरपुर नगर (देवपुर)