

**Electricity Distribution Division Chhibramau
Abstract For PTW Set Connection**

Against Application No. -

Name & Address of consumer Shri/Smt..... **Sudhir Kumar**

C/O/S/o,W/o,Shri/Late.....**Satish Chandra**Name of Village.....**Gugrapur**.....

Post..... **Gugrapur**.....Block..... **Gugrapur**Dis.....**Kannauj**.....

Load Sanction ..13.00 HP ..Sanction.....Date.....

Prosec's...PTW.....Lenth of Line.....H.T.....**40**.....Mtrs...L.T.....Mtrs.....

Name of Scheme.....**Deposit**.....Proposed...13.00 HP....S/S.....**25.KVA**.....

1	Chargeable to consumer :-	
	(a) Fixed Chages for Type service/T/F	Rs.....94582.00
	(i)H.T.Line...40.. X.....@per mtr. Charge	Rs.....9440.00
	(ii) Meter Cost @	Rs.....4957.00
	Total:-108979.00

Certificate :-

Certificate that the connection is beyond the command area of STW Pump canal and is technically feasisit :-

- (i)Nearest distance from existing PTW/Set Electric Diesel.PTW
- (ii)Name of feeder 11 KV.....**Gugrapur**
- (iii)Name of Sub Station 33/11 KV SIS.....**Gugrapur**
- (iv)To the best of my knowledge it is not same porting case.New

Abstract for T.C.

Ch. To consumer Rs.....**108979.00**...

Ch. To Board Rs.....**0.00**...

Total RS.....**108979.00**.....

Detailed Estimate

Sanction No...**D0**...../2023-24.....

Ch. To consumer Rs.....**108979.00**.....

Ch. To Board Rs.....**0.00**.....

G.Total Rs.....**108979.00**....

Checked
D/MAN

Checked

**Sanctioned
Executive Engineer**

mate For Giving

Sudhir Kumar

R/O - Gugrapur

13.00 HP P.T.W. CONNECTION TO

S/o Sri Satish Chandra

Post - Gugrapur

H.T. Line 40 Mtrs

Transformation
25 KVA S/S With D/P

S.No.	Name of Particular	Unit	Quantity	Rate	Amount
1	PCC Pole 8.5 mtr Long	No.	2	2721.00	5442.00
2	Stone Pad	No.	2	140.00	280.00
3	Top Channel 100x50x2240m.m.	No.	1	832.00	832.00
4	Droper Channel 100x50x2028m.m.	No.	1	748.00	748.00
5	"T" off Channel 100x50x1300m.m.	No.	1	478.00	478.00
6	T/F Base Angle 75x75x6x2023m.m.	No.	2	1778.00	3556.00
7	11kv Disc Insulator with disc cutting	No.	6	264.00	1584.00
8	11kv Pin Insulator with G.I. Pin	No.	6	123.00	738.00
9	11/0.4 KV 25 KVAT/F	No.	1	56780.00	56780.00
10	11 KV TPMO	No.	1	18292.00	18292.00
11	Danger Board With Clamp	No.	1	461.00	461.00
12	Stay Rod Complete	No.	3	2027.00	6081.00
13	Earthing Rod	No.	2	838.00	1676.00
14	Holding Clamp for top dropper TP m.etc	No.	11	259.00	2849.00
15	ACSR weasel Conductor	Mtr.	124	23.98	2973.52
Total					102770.52

LINE CHART

11KV Gugrapur from

40 mtr.

Proposed 25KVA T/F

13HP

S/o Sudhir Kumar (S/o Satish Chandra)
Vill + PO - Gugrapur, Kvj

S.D.O.

J.E.