

दूरभाष नं 9193330950

ईमेल:- eecdd2shamli@pvvn.org

ई-मेल/डाक/वाट्सऐप

राष्ट्रहित में बिजली बचाये



कार्यालय

अधिशायी अभियंता

पश्चिमांचल विद्युत वितरण निगम लि०

विद्युत वितरण खण्ड-द्वितीय शामली

निकट 33/11 के०वी० विद्युत उपकेन्द्र खेडीकरमू शामली

पत्रांक/883/वि०वि०ख०द्वि/शामली

दिनांक 30.04/07/23

योजना : जमा योजना

विषय :- पी०टी०डब्लू पोर्टल पर प्राप्त आवेदन संख्या 1008296809 के सापेक्ष 10 अश्व शक्ति का निजी नलकूप विद्युत संयोजन निर्गत करने के संबंध में।

श्री आसिम पुत्र ताहिर हसन

निवासी-कांधला

जनपद शामली।

महोदय/महोदया.

कृपया उपरोक्त विषयक पी०टी०डब्लू पोर्टल पर प्राप्त आवेदन संख्या 1008296809 के सापेक्ष 33/11 के०वी० विद्युत उपकेन्द्र कांधला देहात से पोषित 11 के०वी० पोषक गंगेरु से श्री आसिम पुत्र श्री ताहिर हसन निवासी कांधला को 10 अश्व शक्ति का निजी नलकूप विद्युत संयोजन निर्गत करने हेतु निम्नलिखित धनराशि जमा कराना आवश्यक है।

क्र०स०	विवरण	धनराशि
1	जमानत राशि	3000
2	सेवा संयोजन शुल्क	2036
3	3 फेस मीटर	2921
4	धनराशि जमा योजना के अन्तर्गत	94582
	योग रू०	102539

अतः आपसे निवेदन है कि उक्त धनराशि जमा कराने का कष्ट करे। धनराशि जमा होने के उपरान्त ही अग्रिम कार्यवाही की जा सकेगी।

नियम व शर्त:-

1. आवेदक को उक्त धनराशि आवेदित पी०टी०डब्लू पोर्टल पर ऑनलाईन माध्यम द्वारा जमा करानी होगी।
2. उक्त कार्य नियमानुसार जमा योजना के अन्तर्गत विभागीय नियमानुसार समस्त औपचारिकताएँ पूर्ण कराने के पश्चात ही कराया जायेगा।
3. उपभोक्ता को विद्युत आपूर्ति निर्धारित शैड्यूल के अनुसार दी जायेगी।
4. संयोजन निर्गत करते समय भूमि अथवा परिसर पर लाईन निर्माण करते समय होने वाले किसी वाद विवाद के लिये आवेदक स्वयं जिम्मेदार होगा निगम किसी भी प्रकार के वाद-विवाद के लिये जिम्मेदार नहीं होगा।
5. आर०ओ०डब्ल्यू० उपलब्ध कराने का दायित्व संबन्धित आवेदक/उपभोक्ता का होगा।

(ब्रह्मपाल)

अधिशायी अभियंता

9/1/23

Office of the Sub-Divisional Officer E.D.S.D. II KANDHLA

Name Aashim So/Wo Tahir Hasan PTW Application No. 10.08296809
 Village Kandhla P.O. Kandhla Block Kandhla
 Load 10 H.P. Receipt No. 1799 Date 28.06.2023

S.No.	Work Involved	Qty.	Standard Rate In Rs	Amount(Rs.)	
				For 7.5 H.P	For 10.0 H.P
	Ch. To Consumer				
1	Conversion LT To HT Line (No. Of Pole)		@1000/-per pole	Rs.	Rs.
2	Constraction Of 11 Kv Line On Pcc Pole With Acsr WEASEL Conductor		@236/- per meter	Rs.	Rs.
3	Constraction Of LT Line 3 Phase With Pcc Pole With ACSR Weasel Conductor		@200/- per meter	Rs.	Rs.
4	Construction Of 11/0.4 Kv S/S 25 Kva On Pocc Pole Structure		94582/-	Rs.	Rs. 94582
5	I/C Of Existing S/S.....Kva To.....Kva			Rs.	Rs.
6	(i) 4X25 mm. Armoured PVC Cable With Catenary Arrangement	10 mtr	@213/-per meter	Rs. 2130	Rs. 2130
7	(ii) 3 Phase 4 Wire Static Meter 30-60 Amp. With Meter Box		2921/- per meter	Rs. 2921	Rs. 2921
8	(iii) System Loading Charges		-	Rs. -	Rs. -
9	(iv) Labour & Overhead Charges		₹ 2,036.00	Rs. 2036	Rs. 2036
10	Total Amount			Rs.	Rs.
11	Less Amount of Cable Shall Be Provided By Consumer		Less(-)	Rs. 2130	Rs. 2130
12	Net Amount Ch. To Consumer			Rs.	Rs. 4957
13	Security		300/-per H.P	Rs. 2250	Rs. 3000
14	Total Estimated Amount			Rs.	Rs. 102539

(Sig. Kandhla)
 Junior Engg./Incharge
 33/11 Kv S/S Kandhla dehat

डायरी 1000 दिनांक 04-7-23

- उपस्थंड अधिकारी-प्रथम/द्वितीय
- लेखाकार/सहायक अभियन्ता (रा०)
- कार्यकारी सहायक
- मानचित्रक

No. 1439 /Estimate/PTW

Copy forwarded to the Ex.Eng EDD-II Shamli for information and necessary action certified that the estimate has been prepared as priority

Head Full Deposit
 Estimate Sanction for Rs. 102539
 Ch. To Con. 102539
 Ch. To Corp. 102539
 Total: 102539

Entered In register at S.No:- 41 / 12023 / 2024

Checked
Inde
 D/MAN

A
 DAW)

W
 Executive.Eng.

Dated 03/07/2023

SDD II

Technical Report

1. Length of HT Line Proposed — km
2. Length of LT Line Proposed — km
3. Length of Existing LT Line — km
4. Capacity of Existing S.S. —
5. Capacity Proposed for new S.S. 25 KVA
6. Total Connected Load on S.S. — HP
7. Proposed capacity after increased — KVA
8. Sanctioned load 10 HP
9. Distance of consumer's Site from the nearest sub Division Store 13 K.m.
10. Name of 33/11 KV S.S. Kandhla dehat
11. Name of 11 KV Feeder Congerod

Voltage drop Calculation

The tail point

HP X Km.

Summary of Main Material Require

1. Support (Pole) 2
2. Conductor 25 mtr.
3. Earth wire 6 gauge 05 kg.
4. Stay Wire 10 kg.
5. Pin Insulator With Pin 06
6. Disc Insulator with string 06
7. Stay Rods 2
8. Earth Rods 02
9. Cement —
10. PV Cable —
11. T Clamp 04 nos.
12. Straddle Insulator —
13. Nut & Bolt 02 kg.
14. "V" Type X-arm —
15. J.F. 25 KVA - 01 no.
16. MS Channel 50 kg.
17. MS. Angle 20 kg.

Line Chart

Exist
11KV. Congerod
feeder

HT proposed F.T.W. dip
of Sh. Ashim s/o Tahir
hasan Kandhla
Congerod Road.

Total feasibility HP.Km.

Certified that:-

- 1- The Power loads and voltage drop has been calculated and found to be with in permissible limit
- 2- All the consumer to the Sub-station have been show in line chart
- 3- Boring is complied
- 4- Certified that the site of consumer has been personally inspected by me and above detailed material shall be exclusives & utilized for given connection to this particulars consumer. It is also certified here was no connection previously in this check & no pending aware on this connection
- 5- The double pole with HT Line proposed due to over loaded exist double pole & no LT Line exist near proposed connection.
- 6- The proposed double pole of 25 KVA is justified as per checking of site by me.

Sub-Division Officer
E.D.S.D-II KANDHILA

Jr. Engg./Incharge
33/11 kv S/S. Kandhla dehat

TECHNICAL FEASIBILITY REPORT

1	आवेदक का नाम व पता	
2	आवेदक का क्रमांक	Aashim 40 Tahir Hasan. Kandhla. 1008296809
3	क्या उपरोक्त का भार तकनीकी रूप से निर्गत किया जाना सम्भव है अथवा नहीं ?	Yes.
4	परिसर पर कितने भार की आवश्यकता है ?	10 H.P.
5	विधुत भार किस प्रयोजन हेतु उपयोग किया जायेगा ?	Port. tubewell (LMV)
6	परिवर्तक की क्षमता व उस पर वर्तमान में कितना भार चल रहा है का पूर्ण विवरण।	New 25 KVA 4/F with DIP.
7	33/11 के० वी० उपसंस्थान का नाम	Kandhla dehat
8	33/11 के० वी० उपसंस्थान की क्षमता	2 x 10 MVA.
9	11 के० वी० पोषक का नाम	Gangeron
10	11 के० वी० पोषक पर वर्तमान भार	220 Amp.
11	परिसर पर पूर्व/वर्तमान में यदि कोई संयोजन है /था, तो उसकी संयोजन संख्या	No -
12	पोल नंबर /कोड	-
13	परिसर से नजदीकी एलटी पोल की दूरी	-
14	बुक नंबर	
15	परिसर पर बकाये की स्थिति	1205
16	परिसर पर वाद-विवाद की स्थिति	no -
17	परिसर पर निर्माण कार्य पूर्ण हो गया है अथवा नहीं	no -
नोट	परिसर पर मीटर स्थापना के समय उचित क्षमता का पीवीसी आरमर्ड केबल का प्रबंध उपभोक्ता द्वारा स्वयं किया जायेगा	Yes -

2. Line Chart

5000

fisaa
(अवर अभियन्ता)

33/11 के० वी० विधुत उपकेन्द्र
Kandhla dehat.