


PROJECT ESTIMATE

MADHYANCHAL VIDYUT VITARAN NIGAM LTD.

(A State Government Undertaking)

Head office 4-A, Gokhale Marg, Lucknow 226001
Ph No. 0522-2208737 GSTIN: 09AAECM0108J1ZO



Project Description

: VINODANI W/OVINOD KUMAR VILL-AMRAIYA PO-SEJKHURD BL-PISAWAN
DIST-SITAPUR PTW 8 HP APP-1008290216

Project Code

: MVDP.SI.PD9472

Estimate Value

: 107,994.38

Estimate Printout Date

: 24.06.2023

Previous Approved Version

: N.A.

Fund (Project Code)

: PTW_DEPOSI

SR. NO.	PARTICULARS	UNIT	QTY	RATE(RS.)	AMOUNT
	Material & Service-Lines&Cable - MVDP.SI.PD9472.A				
1	DROPPER CHANNEL 100X50MM - 1800000007	No	1.000	748.00	748.00
2	EARTH ROD 2540X20 MM - 1700000133	No	4.000	838.00	3,352.00
3	11 KV V-TYPE STEEL CROSS-ARM 65X65X6 MM - 2700000161	No	2.000	744.00	1,488.00
4	11KV COMP. POLY. DISC INSULATOR 45KN T&C - 2700000173	No	6.000	412.00	2,472.00
5	TEE-OFF CHANNEL - 1800000012	No	1.000	478.00	478.00
6	11KV F-CLAMP FOR PCC POLE - 2500000048	No	2.000	265.00	530.00
7	HOLDING CLAMP FOR PCC POLE 8.5 MTR. - 2500000002	No	4.000	304.00	1,216.00
8	TOP CHANNEL - 1800000013	No	1.000	826.00	826.00
9	S/S BASE ANGLE FOR T/F 50X50X6MM - 1800000141	No	2.000	1,778.00	3,556.00
10	11 KV COMPOSITE POLYMER PIN INSULATOR - 2700000193	No	9.000	268.00	2,412.00
11	PCC POLE 8.5 MTR.LONG - 1500000000	No	4.000	2,721.00	10,884.00
12	STAY WIRE 7/10 SWG - 2700000071	KG	14.000	84.53	1,183.42
13	STAY SET 16X1800 - 2700000131	No	3.000	2,027.00	6,081.00
14	STAY CLAMP 5½" - 2500000034	PAA	3.000	209.00	627.00
15	G.I.WIRE 6 SWG - 2700000003	KG	6.000	79.07	474.42
16	HOLDING CLAMP FOR TOP/DROPPER CHANNEL - 2500000477	No	5.000	259.00	1,295.00
17	A.C.S.R. WEASEL CONDUCTOR - 1000000028	M	371.000	23.98	8,896.58

अधिसूची अधिनियम
विद्युत वितरण संचालन
सीतापुर



	D 25KVA/11/0.43KV L-II 4 STAR AL. WOUND - 2000000006	No	1.000	56,780.00	56,780.00
	Sub Total - Material (Rs.)				103,299.42
	Total - Material & Service-Lines&Cable - (Rs.)				103,299.42
	T&P Charges - MVDP.SI.PD9472.Q				
1	T&P Charges				1,595.98
	Sub Total - Charges (Rs.)				1,595.98
	Total - T&P Charges - (Rs.)				1,595.98
	Contingency Charges - MVDP.SI.PD9472.Z				
1	Contingency Charges				3,098.98
	Sub Total - Charges (Rs.)				3,098.98
	Total - Contingency Charges - (Rs.)				3,098.98
	Total(Materials + Services + Charges) (Rs.)				107,994.38
	Return Material - MVDP.SI.PD9472.A				
	Grand Total (Rs.)				107,994.38

Amount in Words: One Lakh Seven Thousand Nine Hundred Ninety Four Rupees Thirty Eight Paise Only

(JE-E&M)

Laxmi Narayan

11001274

APPROVED - 24.06.2023

(AE-E&M)


Gyanesh Kumar

11001283

Work Code No. 332321

Sl. No. 268 Year 2023-24

Estimate Amount 107994.00


T.A.


DAW


E.E.