



कार्यालय अधिशासी अभियन्ता,
पश्चिमांचल विद्युत वितरण निगम लि०,
विद्युत वितरण खण्ड
चन्दौसी

Email Id- eddchandausi@gmail.com

CIN NO. U31200UP2003SGC27485

पत्रांक 18271 /विविखचं/तक०
विषय-धनराशि जमा करने के सम्बन्ध में।

दिनांक 8-12-23

श्री टीकम सिंह पुत्र श्री वीरेन्द्र सिंह
पता/साईट-गाटा सं० 75, वहादुर नगर,
ब्लाक-बहजोई।

मो०नं०- 9997101894

आपको सूचित किया जाता है कि इस कार्यालय के रू० 100 रसिद सं०/चालान नं० 1008356937 दिनांक 03/12/2023 के द्वारा जमा योजना में स्वीकृत संयोजन 10 किवा/एचपी/केवीए के स्थायी नलकूप (LMV-5) विद्युत संयोजन को देने हेतु निम्नलिखित व्यय होगा।

कृपया आपसे निवेदन है कि निम्नलिखित धनराशि इस पत्र में अंकित विवरण के अनुसार अधिकतम तीन माह के अन्दर जमा कराये अन्यथा ये समझा जायेगा कि आप विद्युत संयोजन लेने के इच्छुक नहीं है और आपकी स्वीकृति रद्द कर दी जायेगी।

क्र०सं०	विवरण	जमा योजना
1.	जमानत राशि	3000.00
2.	(S.C Charge)	2036.00
3.	मीटर धनराशि	2921.00
4.	प्राक्कलन धनराशि	96942.00
	कुल योग	104899.00

- रू० जमा करने के पश्चात अपनी रसीद इस कार्यालय से 100/- के नॉनजुडिशियल स्टाम्प व पांच रुपये की रसीद टिकिट अपने दो गवाहों तथा अपने सब सहित इस कार्यालय में अनुबन्ध करें।
- फिटिंग रिपोर्ट तथा बैंक चालान फार्म अनुबन्ध के समय इस कार्यालय में जमा करें।
- पूर्ण जमा योजना के अन्तर्गत जमा राशि बाद में देय नहीं है।
- बोरिंग स्थल पर मीटर लगाने हेतु एक कमरे का निर्माण कराना सुनिश्चित करें।

अधिशासी अभियन्ता

ESTIMATE PTW.

Pro.Fee R.NO.	100	Pro.Fee Amount	100.00
Date	01/11/2023	Scheme	DEPOSIT
Estimate framed by	SDO III EDS-III BAHJOI		
For giving supply to Sh.	TEEKAM SINGH	S/O SH.	VIRENDRA SINGH
Village	BAHADUR NAGAR	P.O	KHAS
Block	BAHJOI	Distt. Sambhal	
Load	10 HP. Ptw. Process .		
1.11KV Line	10 Mtr. on Pcc supports @Rs.	236 per mtr.	Rs. 2360.00
2.LT Line3Ph.	0 Mtr.. on Pcc supports @Rs.	200 per mtr.	Rs. 0.00
3.Extra cost of HT connection with HT line or Toff from HT line			Rs.
4.Extra cost of HT connection with S/S			Rs.
5.Extra cost of LT connection with LT main line			Rs.
6.Extra cost of LT connection with upto 25KVA S/S		COST OF 25 Kva S/S	Rs. 94582.00
7.Extra cost for terminal pole fitting			Rs.
8.Extra cost for Road / Telephone line Crossing for HT line			Rs.
9.HT line / LT line Inspection fee			Rs.
Total-Rs.			96942.00

10.Length of line ch.to Corporation.....	Meters	
11.Length of line ch.to Consumer....	10 Meters	
(Beyond free Limit of 190 meters)		
Total	10 Meters	Ch.to Crop. / PC
12.(a)11/0.4KV S/S.....25.....KVA vide Schedule No.	Ch. To PC	Rs.
13.Electric Inspection of T/F		Rs. 4957
14.System Loading charges		Rs.
15.Fixed charges		Rs.

The HT Line/LT Line will be tapped from SOUTH E fdr. S/S in Vill. BAHADUR NAGAR
 Connection from 33/11KV S/S at BAHJOI

Certified that the cosing of work involved has been done according to standard schedule framed in division
 On current stock issue rate.

(line chart on its back)

Sanctioned Amount forRs. 101899
 S No. for financial year

Classified as under :

- (a) Ch. To board
 - (i) Transmission Rs. 101899=00
 - (ii) Transformation Rs. Sanctioned For Rs. 2020
 - (iii) Distribution Rs. 00000. One Eight Thirteen
- (b) Ch. To Consumer
 - (i) Transmission Rs. Sanction No. & Date
 - (ii) Transformation Rs. Ch. To. Deptt. Rs. will
 - (iii) Distribution Rs. P.G. Rs. 101899=00

Checked by


DRAFTS MAN


J.E.



S.D.O

D.A(W)


 Ex. Engr.
 Elect. Distr. Division
 Chandausi
Executive Engineer

DETAIL LINE CHART

PROPOSED 25 KVA T/F TO TEEKAM
SINGH S/O VIRENDRA SINGH
VILL - BAHADUR NAGAR

VOLTAGE DROP :-

Surveyed by shri


JAIVIR SINGH


(A) List of Material

(B) Details

01.Pcc Pole	NO.	2	1.Length of Live (a)HT.	10	MTR
02. ACSR Weasel con.	MTR	35	(b)LT.	0	MTR
03. Stay Rod 16x1800mm	NO.	2	2.Existing capacity of S/S	0	KVA
04. Stay Wire 7/10 SWG	KG.	25	3.Existing Load	0	HP
05. Earthing rod	NO.	2	4.Proposed Load	10	HP
06. 11kv disc Insulator	NO.	6	5.Proposed capacity of S/S	25	KVA
07. 11 kv disc fitting	NO.	6			
08. 11 kv pin Insulator	NO.	3			
09. 11 kv pin with Nut	NO.	3			
10. 11 kv x-arm v- type	NO.	0			
11. M.S.channel 100x50x6mm	KG.	44			
12. M.S.angle 65x65x6mm	KG.	26			
13. 11/0.4kv 25 kva T/F	NO.	1			

Proposed By


Junior Engineer


Sub-Divisional Officer

G/S TO SH.

TEEKAM SINGH

S/O SH. VIRENDRA SINGH

VILL. BAHADUR NAGAR

**PASHCHIMANCHAL VIDYUT VITRAN NIGAM LTD.
JOB CARD**

PTW

(A) HT. LINE

10

MTR.

(C) NEW S/S 25 KVA W/O NO. & DATE STARTING DATE

(B) LT. LINE

0

MTR.

(D) INCREASING CAPTY. KVA TO KVA COMPLETION DATE

Sl. NO.	ITEM DESCRIPTION	ITEM CODE	UNIT CODE	ESTIMATED QTY.		QUANTITY ISSUED/RETURNED				NET QTY. ISSUED
				ORIGINAL	REVISED	ISSUE NO. DT.	ISSUE NO. DT.	ISSUE NO. DT.	ISSUE NO. DT.	
1	Pcc Pole 8.5 mtr. long	H000557	01	NO.	2					
2	ACSR Weasel cond.	H300909	10	MTR..	35					
3	Slay Rod 16x1800 mm		10	NO.	2					
4	Slay Wire 7/10 SWG		07	KG.	25					
5	Earthing rod		07	NO.	2					
6	11kv Disc Insulator		01	NO.	6					
7	11kv Disc Fitting		01	NO.	6					
8	11kv Pin Insulator		15	NO.	3					
9	11kv Pin with Nut		01	NO.	3					
10	11kv X-Arm V Type		01	NO.	0					
11	M.S. Channel 100x50x6 mm		09	KG.	44					
12	M.S. Angle 65x65x6 mm		01	KG.	26					
13	11/0.4 kv 25 kva T/F			NO.	1					
14										
15										

NAME OF ESTIMATE

ESTIMATE NO.

FIELD SUB DIV. NAME

P.T.O