

सेवा में

अधिसूचनी अधिसूचना
विद्युत वितरण संचयन द्वितीय,
हरदोई

App. No. - 1008310985

महोदय

दिनांक -

आवेदक का नाम एवं पता :-

कृपया आपके जनसौजन्य पत्रोंक-

जो कि विद्युत भार स्वीकृत हेतु आख्या प्रस्तुत किये जाने से सम्बन्धित है।

विद्युत वितरण संचयन द्वितीय दरदाई नगरी मंडला

Suresh Chandra S/o Nanda
R/o. villa. Ucharal Hariganam

1. उपरोक्त कनेक्शन शहरी क्षेत्र/नगर पंचायत क्षेत्र की सीमा के अर्न्तगत है या बाहर ? **बाहर**
2. विद्युत संयोजन देने हेतु प्रस्तावित लाइन प्राथमिक फीडर से जोड़ी जा रही है या टाउन फीडर **प्राथमिक फीडर** से ?
3. क्या प्रस्तावित संयोजन हेतु उपभोक्ता का परिसर निर्मित है ? उसके पूर्व से कोई अन्य **परिसर जोड़ा नहीं है** कनेक्शन किसी अन्य से तो नहीं है या था ?
4. क्या कनेक्शन देने हेतु डीपीओ परिसर के बाहर बनाया जाना सुनिश्चित किया जाता है ? **हाँ**
5. निम्नलिखित त्तन परिसर के मेन गेट के पास अलग से बाह्य एवं मात्र एक दरवाजा के साथ **जोड़ा नहीं** सुनिश्चित किया गया है ?
6. संयोजन अद्युक्त करने हेतु वोल्टेज क्या है ? **440V**
7. ट्री/एक विभाग का है या उपभोक्ता का ? **उपभोक्ता का**
8. ट्री/एक की कैपेसिटी क्या है ? **25KVA TIF Proposed**
9. गलत लाइन आरंभ (सिंगल लाइन डायग्राम)। **1.20m**


11KV Line Existing Submarine Feeder



0.30m

0.50m

50m



Suresh Chandra
S/o
Nanda

संस्तुति - आवेदक/उपभोक्ता को

Balramkumar Jain
जो 05/0
33/11 KV SIS
Hariganam


एस10डी10300



PROJECT ESTIMATE
MADHYANCHAL VIDYUT VITARAN NIGAM LTD.
 (A State Government Undertaking)
 Head office 4-A, Gokhale Marg, Lucknow 226001
 Ph No. 0522-2208737 GSTIN: 09AAECM0108J1ZO

Project Description : PTW OF SURESH CHANDRA 1008310985
 Project Code : MVDP.HR.PD9089
 Estimate Value : 109,485.66
 Estimate Printout Date : 11.08.2023
 Previous Approved Version : N.A.
 Fund (Project Code) : PTW_DEP0SI

SR. NO.	PARTICULARS	UNIT	QTY	RATE(RS.)	AMOUNT
	Material & Service-Lines&Cable - MVDP.HR.PD9089.A				
1	A.C.S.R. WEASEL CONDUCTOR - 1000000028	M	400.000	24.00	9,600.00
2	11 KV V-TYPE STEEL CROSS-ARM 65X65X6 MM - 2700000161	No	2.000	744.00	1,488.00
3	M.S. ANGLE 65X65X6 M.M. - 1800000000	KG	24.000	148.00	3,552.00
4	G.I WIRE 10 SWG - 2700000005	KG	18.000	111.00	888.00 1332.00
5	STAY SET 16X1800 - 2700000151	No	3.000	519.00 1000.00	1617.00 3000.00
6	STAY INSULATOR - 2700000012	No	3.000	150.00	450.00
7	STONE PAD 300X300X75MM - 2700000147	No	4.000	140.00	560.00
8	11 KV COMPOSITE POLYMER PIN INSULATOR - 2700000195	No	12.000	268.00	3,216.00
9	PCC POLE 8.5 MTR.LONG - 1500000000	No	4.000	2,721.00	10,884.00
10	EARTH ROD 2540X20 MM - 1700000135	No	3.000	503.00	1,509.00
11	HOLDING CLAMP FOR PCC POLE 8.5 MTR. - 2500000002	No	12.000	304.00	3,648.00
12	M.S CHANNEL 100X50X5 M.M. - 1800000001	KG	55.000	150.00	8,250.00
13	STAY WIRE 7/10 SWG - 2700000071	KG	15.000	81.20 145.40	1,098.76 2181.00
14	11KV COMP. POLY. DISC INSULATOR 45KN T&C - 2700000173	No	6.000	264.00	1,584.00
15	11KV F-CLAMP FOR PCC POLE - 2500000048	No	2.000	265.00	530.00
16	STAY CLAMP 5 1/2" - 2500000054	PAA	3.000	204.00 150.00	612.00 450.00
	Sub Total - Material (Rs.)				19,516.76 52234.00

Total - Material & Service-Lines&Cable - (Rs.)			40,516.76
Material & Service-Plant&Machinery - MVDP.HR.PD9089.B			
1	TD 25KVA/11/0.43KV L-II 4 STAR AL WOUND - 20000000006	No 1.000	56,780.00
Sub Total - Material (Rs.)			56,780.00
Total - Material & Service-Plant&Machinery - (Rs.)			109,014.00
Contingency Charges - MVDP.HR.PD9089.Z			
1	Contingency Charges		3,270.00
Sub Total - Charges (Rs.)			3,188.90
Total - Contingency Charges - (Rs.)			3,188.90
Total(Materials + Services + Charges) (Rs.)			109,485.60
Return Material - MVDP.HR.PD9089.A			
Grand Total (Rs.)			109,485.60

Amount in Words: One Lakh Nine Thousand Four Hundred Eighty Five Rupees Sixty Six Paise Only 112284.00

Balmukund Rai
 (Junior Engineer)
 Balmukund Rai
 11008201
 APPROVED - 11.08 2023

Kuldeep Singh
 (AE-E&M)
 Kuldeep Singh
 11001355

Chb. Head... *DTWP-Set*
 Sanction No SBD/..... *19023-24*
 Chb. To UPPCL Rs.. *NIL*
 Chb. To Consumer Rs. *112284.00*
TOTAL Rs 112284.00
Rs. One lac. Twelve. Two hundred two thousand Eighty four only

LXJ Eng.
 FDD, Shahabad, Hardoi
[Signature]