


PROJECT ESTIMATE



DAKSHINANCHAL VIDYUT VITARAN NIGAM LTD.

(A State Government Undertaking)

Urja Bhavan, Nh-2 (Agra - Delhi Bypass Road), Sikandra, Agra - 282002
Ph No. 1800 180 3023 GSTIN: 09AACCD06950125

मुहम्मदी मंसूर खान

Project Description : RAMSIYAW/OSHYAMKISHOR-DHANJA-1008368392

Project Code : DVDP.JL.PD6450

Estimate Value : 195,841.99

Estimate Printout Date : 25.01.2024

Previous Approved Version : N.A.

Fund (Project Code) : PIW_DEP051

9935169370

1008368392

10HP

13.01.2024

SR. NO.	PARTICULARS	UNIT	QTY	RATE(RS.)	AMOUNT
	Material & Service-Lines&Cable - DVDP.JL.PD6450.A				
1	11 KV DP Clamp for PCC Pole 8.5 Mtr - 2500000238	No	4.000	✓ 304.00	1,216.00
2	11 KV Stay Clamp for PCC Pole 8.5 M long - 2500000309	No	4.000	✓ 527.00	2,108.00
3	EARTH ROD 2540X20 MM - 1700000133	No	10.000	✓ 538.00	5,380.00
4	11 KV COMPOSITE POLYMER PIN INSULATOR - 2700000193	No	27.000	✓ 123.00	3,321.00
5	11 KV F Clamp for PCC Pole 8.5 Mtr Long - 2500000339	No	8.000	✓ 304.00	2,432.00
6	MS T-OFF CHANNEL 100X50X5X1300 MM - 1800000099	No	2.000	✓ 478.00	956.00
7	A C.S.R. WEASEL CONDUCTOR - 1000000028	M	1500.000	✓ 23.90	35,970.00
8	M.S. Top Channel 100x50x5x2240 mm - 1800000092	No	1.000	✓ 832.00	832.00
9	Nut-Bolts for Clamps & Channels - 2500000288	No	36.000	✓ 259.00	9,324.00
10	11 KV Cross Arm Clamp for PCC Pole 8.5 M - 2500000361	No	8.000	✓ 304.00	2,432.00
11	11 KV TPMO WITH POLYMER INSULATOR - 2700000357	No	3.000	✓ 6,097.33	18,291.99
12	Stay Set Galvanised 16x1800 as pr ann-1 - 2700000515	No	4.000	✓ 800.00	3,200.00
13	G.I.WIRE 10 SWG - 2700000005	KG	20.000	✓ 150.00	3,000.00
14	PCC POLE 8.5 MTR.LONG - 1500000000	No	10.000	✓ 2,721.00	27,210.00
15	11 KV STAY LOOP INSULATOR - 2700000271	No	4.000	✓ 200.00	800.00
16	M.S. DROPPER CHANNEL 100X50X5X2028 MM - 1800000115	No	1.000	✓ 748.00	748.00
17	DISC FITTING 45KN (T&C) - 1700000374	No	9.000	✓ 97.00	873.00

Singh
SDO *(Signature)*

18	11 KV POLYMER DISC INSULATOR (T&C) 45 KN - 1400001023	No	9.000	167.00	1,503.00
19	T-F BASE ANGLE 65X65X6X2028 MM - 2700000355	No	2.000	1,728.00	3,556.00
20	11 KV V-TYPE STEEL CROSS-ARM 65X65X6 MM - 2700000161	No	8.000	744.00	5,952.00
21	STAY WIRE 7/10 SWG - 2700000071	KG	20.000	100.00	2,000.00
Sub Total - Material (Rs.)					131,104.99
Total - Material & Service-Lines&Cable - (Rs.)					131,104.99
Material & Service-Plant&Machinery - DVDP.JL.PD6450.B					
1	1D 25KVA/11.0.43KV L-II 4 STAR AL. WOUND - 2000000006	No	1.000	56,780.00	56,780.00
Sub Total - Material (Rs.)					56,780.00
Total - Material & Service-Plant&Machinery - (Rs.)					56,780.00
Material-Meter - DVDP.JL.PD6450.C					
1	ENER. MET. ELE. #10-60 3 PH. W. MET. BOX - 1300000160	No	1.000	2,921.00	2,921.00
Sub Total - Material (Rs.)					2,921.00
Total - Material-Meter - (Rs.)					2,921.00
SECURITY&FIX CHARGE - DVDP.JL.PD6450.Z					
1	FIXED CHARGE				2,036.00
2	SECURITY CHARGE				3,000.00
Sub Total - Charges (Rs.)					5,036.00
Total - SECURITY&FIX CHARGE - (Rs.)					5,036.00
Total(Materials + Services + Charges) (Rs.)					195,841.99
Return Material - DVDP.JL.PD6450.A					
Grand Total (Rs.)					195,841.99

Amount in Words: One Lakh Ninety Five Thousand Eight Hundred Forty One Rupees Ninety Nine Paise Only 68000

127841.00

Sanction No. 12024.25/10/11/8122
 CHARGABLE TO DEPT. 68000.00
 CHARGABLE TO CONSUMER 127841.00
 SANCTION TO AMMOUNT-195841.00

Y. K. JET
(Ex. Eng.)